



Stability of point process spiking neuron models

Yu Chen¹ · Qi Xin² · Valérie Ventura¹ · Robert E. Kass¹

Received: 26 January 2018 / Revised: 27 August 2018 / Accepted: 30 August 2018 / Published online: 15 September 2018
© Springer Science+Business Media, LLC, part of Springer Nature 2018

Abstract

Point process regression models, based on generalized linear model (GLM) technology, have been widely used for spike train analysis, but a recent paper by Gerhard et al. described a kind of instability, in which fitted models can generate simulated spike trains with explosive firing rates. We analyze the problem by extending the methods of Gerhard et al. First, we improve their instability diagnostic and extend it to a wider class of models. Next, we point out some common situations in which instability can be traced to model lack of fit. Finally, we investigate distinctions between models that use a single filter to represent the effects of all spikes prior to any particular time t , as in a 2008 paper by Pillow et al., and those that allow different filters for each spike prior to time t , as in a 2001 paper by Kass and Ventura. We re-analyze the data sets used by Gerhard et al., introduce an additional data set that exhibits bursting, and use a well-known model described by Izhikevich to simulate spike trains from various ground truth scenarios. We conclude that models with multiple filters tend to avoid instability, but there are unlikely to be universal rules. Instead, care in data fitting is required and models need to be assessed for each unique set of data.

Keywords Generalized linear model · Outlier trials · Point process regression · Spike train

1 Introduction

Point process regression models based on the framework of generalized linear models (GLMs) have been applied to a wide variety of spiking neuron data ((Kass et al. 2014; Weber and Pillow 2017), and references therein). These models, which may be considered nonlinear Hawkes processes (Chen et al. 2017; Eichler et al. 2017), allow neural firing rates to depend on spiking history. Recently, however, Gerhard et al. (2017) reported that models fitted to real data sets could be unstable in the sense that their firing rates could evolve to become arbitrarily large, generating unrealistic spike trains, even when standard goodness-of-fit tests fail to identify lack of fit (see Fig. 1 for two examples).

In this paper we identify several factors that can lead to this problem, we provide additional analysis for diagnosing it, and we present methods to improve model stability.

In some circumstances, causes of instability are easy to identify and easy to fix. The problem of stability, however, leads naturally to an interesting detail in GLM-type modeling of spike trains. When spike trains are modeled as point processes, the firing rate is defined by the conditional intensity function

$$\lambda(t|H_t) = \lim_{\Delta t \rightarrow 0} \frac{\mathbb{P}(\Delta N_{(t, t+\Delta t]} = 1 | H_t)}{\Delta t} \quad (1)$$

where H_t is the set of spikes prior to time t , known as the spiking history up to time t , and $\Delta N_{(t, t+\Delta t]}$ is the number of spikes in the interval $(t, t+\Delta t]$. This succinct representation can also incorporate stimulus effects and coupling effects and its implementation can take advantage of a large body of knowledge about generalized regression models (Kass et al. 2014). Here we only consider the history effects without external stimulus and coupling neurons. There are many ways to capture the effects of the history H_t on the intensity. Letting t_{j*} be the j th spike time counting backwards prior to time t , a concise and intuitive assumption, for

Action Editor: Jonathan Pillow

Yu Chen and Qi Xin have contributed equally to this paper

✉ Yu Chen
yuc2@andrew.cmu.edu

¹ Carnegie Mellon University, Pittsburgh, PA 15213, USA

² University of Science and Technology of China, Hefei, Anhui 230026, China




Fig. 1 Simulation divergence of FLF models (Eq. (4)) fitted to data. **(a, d)** Spike time raster plot and PSTH for datasets *Monkey-PMv* and *Human-Cortex*. **(b, e)** The fitted FLF models pass the original and discrete KS tests of Brown et al. (2002) and Haslinger et al. (2010); the two tests overlap so they are hard to distinguish. **(c, f)** Spike time raster plot and PSTH of spike trains simulated from the fitted FLF

models, using algorithm 2 in Appendix C. **c** If the simulation lasts longer than the training session, the firing rate keeps growing to produce ISIs that are shorter than the refractory period. **f** The simulated spike trains resemble the observed data except for trials 2 and 4, which have many more spikes than the observed spike trains

steady-state scenarios (where the baseline rate is constant), takes the intensity to have the form

$$\log \lambda(t|H_t) = \beta_0 + \sum_j h(t - t_{j*}) \tag{2}$$

where $h(u)$ is a smooth function, and the summation extends to all spikes that precede time t (within a given trial, if there are trials). This is the form used by Pillow et al. (2008) and Gerhard et al. (2017). Pillow et al. (2008) referred to $h(u)$ as a post-spike filter. An alternative model, used by Kass and Ventura (2001), instead allows the effects of each previous spike to be different:

$$\log \lambda(t|H_t) = \beta_0 + \sum_{j=1}^k h_j(t - t_{j*}). \tag{3}$$

If each function h_j involves separate free parameters, then the model in (3) would typically have more parameters than the model in (2). A main contribution of this paper is to

describe situations under which this additional flexibility can be useful. In particular, we suggest that, in realistic scenarios, models of the form (3) tend to be stable.

One issue in using (3) is that the number of terms k must be selected. In theory the number could be infinite as long as a suitable condition is placed on the functions h_j , such as $\sum M_j < \infty$, where $M_j = \max_u h_j(u)$, but in practice (Kass and Ventura 2001) selected k by applying the likelihood ratio test; here, in Section 4, we will suggest another criterion, based on stability. Similarly, in practice, the summation in (2) extends over a fixed window of time preceding t , having length we label T_h (at most, the total length of the experiment), leading to the alternative representation

$$\log \lambda(t|H_t) = \beta_0 + \sum_{t_{j*} \in (t-T_h, t]} h(t - t_{j*}). \tag{4}$$

We refer to a model described by (4) as Fixed Length Filter (FLF), and those described by (3) as Fixed Number Filter

(FNF), where the fixed number refers to the fixed number of spikes. In our analysis we have found it useful to further categorize FNF models by considering the special case in which $h_j(u) = h_1(u)$, for all j and all u . These models we write these as FNF_S, where S stands for single filter. The more general case we write as FNF_M, with M for multiple. Note that FNF_S differs from FLF in that the number of spikes is fixed rather than the length of the time interval, but both models use a single filter while FLF_M uses multiple filters.

We begin, in Section 2, by giving some analytical stability results along the lines of those in Gerhard et al. (2017). In Section 3 we identify several kinds of model misspecification that lead to instability, and we note potential solutions. In Section 4 we focus on FNF models and the variation that replaces the constant β_0 with a time-varying function $\beta(t)$. An analytical diagnostic method is then used to select the number of previous spikes to be considered in the model, i.e., the number of terms k in (3). In Section 5, we compare FLF and FNF models. We close in Section 6 with advice on the use of these models.

2 Stability analysis

Figure 1 shows two examples of unstable simulations from FLF models (Eq. (4)) fitted to the *Monkey-PMv* and *Human-Cortex* datasets described in Table 1, Appendix A, using the smooth basis method of Pillow et al. (2008). The fitted FLF models pass the original and discrete KS goodness of fit tests Brown et al. (2002) and Haslinger et al. (2010) but they are unstable, in the sense that the firing rates of some or all the simulated spike trains evolve to become arbitrarily large, generating unrealistic spike trains. We emphasize that instability is not a matter of extrapolation to unseen data outside the experimental range of time. Rather, if a model is unstable, in simulations it can evolve to producing firing rates far in excess of those seen in real data, which makes it patently unrealistic as a representation of neural physiology.

Gerhard et al. (2017) argue that a reliable diagnostic of model instability can be obtained from the relationship between the firing rate A_0 before the last spike at t_{1*} in an interval, and the firing rate after t_{1*} . They approximate A_0 with the average firing rate in the interval $(t - T_h, t_{1*})$. Then they rewrite the fitted FLF model (Eq. (4)) as

$$\begin{aligned} \log \lambda(t|H_t) &= \beta_0 + h(t - t_{1*}) + \sum_{t_{j*} \in (t - T_h, t_{1*})} h(t - t_{j*}), \end{aligned}$$

and approximate the summation by its expectation under the assumption that the point process in the interval $(t - T_h, t_{1*})$ is homogeneous Poisson, yielding

$$\begin{aligned} \log \lambda(t|H_t) &\approx \beta_0 + h(t - t_{1*}) + A_0 \int_{t - T_h}^{t_{1*}} (e^{h(u)} - 1) du. \end{aligned} \tag{5}$$

Gerhard et al. (2017) then use (5) to derive the approximate PDF of the future ISI $t_* - t_{1*}$, where t_* is the time of the next spike after t_{1*} , and calculate the firing rate after t_{1*} as the reciprocal of the mean future ISI:

$$\mathcal{L}_h(A_0) = \frac{1}{\mathbb{E}[t_* - t_{1*}]}. \tag{6}$$

Equation (6) is a function of A_0 because Eq. (5) is a function of A_0 . The instability diagnostic is obtained by plotting $\mathcal{L}_h(A_0)$ versus A_0 , as in Fig. 2b, for $A_0 \in [0, \lambda_{max}]$, where λ_{max} is the maximum possible firing rate. Without loss of generality, in this paper we do not build a refractory period in the models we consider, except to reproduce (Gerhard et al. 2017) Fig. 4 (see Appendix B Fig. 9), so λ_{max} is our simulation resolution of 1000 spikes per second. We examine intersections of the diagnostic curve with the secant line $\mathcal{L}_h(A_0) = A_0$, referring to them as *cross points*.

A model is deemed

- **divergent** if all cross points exceed λ_{thr} or $\mathcal{L}_h(A_0)$ is always larger than A_0 (e.g. Fig. 2b, red curve), where λ_{thr} is a threshold rate judged too high physiologically; here we used $\lambda_{thr} = 0.9 \cdot \lambda_{max}$ spikes/sec;
- **stable** if the number of cross points is odd and they are all below λ_{thr} (green curve);
- **fragile** otherwise (blue curve).

Note that the diagnostic green curve in Fig. 2b exceeds the first secant for small values of A_0 , which is desirable because otherwise the firing rate would eventually decrease down to zero. A divergent model yields unstable simulations, whereas spike trains simulated from a fragile model might first look stable and then degenerate. Therefore the difference between divergent and fragile models is the duration it takes for spike trains to become unstable. Without loss of generality of our results, we do not distinguish between divergent and fragile models, and consider them both unstable.

Gerhard et al. (2017) validated their model stability diagnostic against spike train data: they considered a model




Fig. 2 (b) Three diagnostic curves corresponding to the three FLF models (equation 4) with baseline rates $\beta_0 = -4$ and filters $h(t)$ shown in (a) in matching colors, where $h(t) = \beta_1 \cdot B_1(t) + \beta_2 \cdot B_2(t)$, $B_1(t) = e^{-t/0.02}$ and $B_2(t) = e^{-t/0.1}$ are the smooth basis

functions used in Pillow et al. (2008) and shown in the insert in (a), and $T_h = 0.35$ sec. The values of (β_1, β_2) for the three models are marked as crosses in (c). c Diagnostic map for the above model as β_1 and β_2 vary

family F_θ parametrized by θ , and for each value of θ in a range, they (i) simulated a 10 sec. long spike train from F_θ (e.g. using algorithm 2 in Appendix C), and deemed the spike train unstable if the model generated over $0.9 \cdot \lambda_{max}$ spikes in the last second, (ii) produced the diagnostic curve and determined from it if the model was stable, fragile, or divergent and (iii) plotted θ against the outcomes in (i) and (ii). Figure 9, Appendix B, shows these plots for two model families F_θ . Figure 9a shows the same stability map as in Gerhard et al. (2017) Fig. 4, where F_θ is an FLF model (Eq. (4)) with baseline rate $\beta_0 = -5.3$ and filter $h(t) = \beta_1 \cdot B_1(t) + \beta_2 \cdot B_2(t) + \text{Dip}(t)$, $\theta = (\beta_1, \beta_2)$, $B_1(t) = e^{-t/0.02}$ and $B_2(t) = e^{-t/0.1}$ are the smooth basis functions used in Pillow et al. (2008) and shown in the insert in Fig. 2a, $\text{Dip}(t)$ is a negative window function modeling a 2 msec. refractory period, and the filter length is $T_h = 0.2$ sec. In Fig. 9c, F_θ is an FLF model with baseline rate $\beta_0 = -4$, filter $h(t) = \beta_1 \cdot B_1(t) + \beta_2 \cdot B_2(t)$ with $B_1(t)$ and $B_2(t)$ defined above, and filter length $T_h = 0.35$ sec.

The stability maps in Fig. 9a and c suggest that the diagnostic is mostly reliable, except in small regions of the parameter spaces. This happens because Gerhard et al. (2017) replaced $h(u)$ by the Taylor expansion ($\exp h(u) - 1$) in (5), which is accurate only when $h(u)$ is small. Without this approximation, (5) becomes

$$\log \lambda(t|H_t) \approx \beta_0 + h(t - t_{1*}) + A_0 \int_{t-t_{1*}}^{T_h} h(u)du, \tag{7}$$

and the diagnostic is still tractable, as shown in Appendix D. Figure 9b and d show the updated stability maps based on (7). The agreement between diagnostic and simulation is very close, and closer than in Fig. 9a and c, so we use the

updated diagnostic in the rest of the paper. Figure 9d is reproduced in Fig. 2c.

To solve the stability problem when a model is found to be divergent or fragile, Gerhard et al. (2017) suggest stabilizing it by refitting to the data with the constraint that its parameters lie in the stable region of the parameter space. In the next section, we identify three data features that might lead to unstable simulation models, namely small sample size, time varying firing rates, and trial to trial variability or outlier trials, and we provide alternative suggestions for stabilization: collecting more data, fitting inhomogeneous rate models, and removing outliers, respectively.

3 Special cases of FLF model instability

A feature that might lead to unstable models is a small sample size. Indeed fitting a model to a small dataset yields parameter estimates that have large variances and, therefore, that could lie in unstable regions of the parameter space by chance, even if the true parameters lie in stable regions. Collecting more data, if possible, would reduce the variability of parameter estimates and stabilize the model.

Next, consider the *Monkey-PMv*, shown in Fig. 1a. An FLF model fitted to the data satisfies the KS goodness-of-fit tests (Fig. 1b), yet simulations from the model diverge (Fig. 1c). Because the peri-stimulus time histogram (PSTH) in Fig. 1a appears to increase, we fit a time-varying baseline rate $\beta(t)$ in place of β_0 in (4). That model fits the data somewhat better according to a likelihood ratio test ($p = 0.046$), and data simulated from it do not diverge (Fig. 3c). (To simulate data past the maximum experimental time of one second, we set $\beta(t) = \beta(1)$ for $t \geq 1$ sec.) Fig. 3d, e and f shows a similar outcome when we apply the same




Fig. 3 Stability of FLF models (Eq. (4)) with constant and time varying baseline firing rates. **a** Constant (blue) and time varying (red) baseline rates of FLF models fitted to the *Monkey-PMv* data: the baseline appears to vary. A likelihood ratio test confirms that the time varying baseline model fits the data significantly better ($p = 0.046$). **b** Fitted filters of the constant and time-varying baseline models. **c** PSTHs of the observed data and of data simulated from the fitted homogeneous and inhomogeneous FLF models: the homogeneous model simulates unstable spike trains; the inhomogeneous model is simulation stable.

d, e, f Same analysis applied to artificial data generated from an inhomogeneous *Izhikevich* model (algorithm 1 in Appendix C; Izhikevich 2003, 2004). **d** Data raster plot. **e** Fitted filters of the homogeneous and inhomogeneous baseline FLF models: the latter is mostly below the former, which may reduce the chance of unstable simulated spike trains. **f** Indeed, the homogeneous model produces data whose rate diverges; the inhomogeneous model appears to be stable. Note that the inhomogeneous model fits the data significantly better according to a likelihood ratio test ($p \ll 0.001$)

analysis to synthetic data generated from an inhomogeneous *Izhikevich* model (algorithm 1, Appendix B). Hence, in the presence of a time-varying trial-averaged rate, fitting a constant rate term can produce instability and fitting a time-varying rate can rectify the problem.

Finally, consider the *Human-Cortex* data displayed in Fig. 1d. An FLF model fitted to the data satisfies the KS goodness-of-fit tests (Fig. 1e) but two out of ten spike trains simulated from it diverge (Fig. 1f). Figure 4a shows that trials 8, 9, and 10 have rather large spike counts compared to the others, so there might be excess trial-to-trial variability or outlier trials that might cause the instability. To examine the extent to which some trials may be unusually different than others, we compute the distance of each spike train from a central spike train \overline{ST} (defined below) based on a spike train metric devised by Wu and Srivastava (2011). This metric measures the discrepancy between two spike trains by counting the number of spikes in one spike train that can be matched by spikes in the other spike train using

a smooth deformation of time, or “time-warping function.” If there are N_1 and N_2 spikes in two spike trains ST_1 and ST_2 , the distance between the two spike trains is defined as

$$d(ST_1, ST_2) = \inf_{\gamma \in \Gamma} \left(N_1 + N_2 - 2 \sum_{i=1}^{N_1} \sum_{j=1}^{N_2} I_{[t_i = \gamma(s_j)]} + \eta \int_0^T \left(1 - \sqrt{\gamma'(t)} \right)^2 dt \right), \tag{8}$$

where I is the indicator function, t_i and s_j are spike times from ST_1 and ST_2 , respectively, and $\Gamma(t)$ is the set of all continuous and piecewise differentiable time warping functions γ such that $\gamma(0) = 0$, $\gamma(T) = T$, and $0 < \gamma'(T) < \infty$. In practice γ is approximated by a piecewise linear function from $[0, 0]$ to $[T, T]$ in a discrete grid and the tuning parameter η is set to $(N_1 + N_2) \cdot c/2T$, with $5 \leq c \leq 25$ (Wu and Srivastava 2011). The choice of c in this range has little impact on results. The first term on the right hand side of (8) measures how close ST_1 is to the




Fig. 4 Trial-to-trial variability affects simulation stability. **a** Spike train counts and deviations from the central spike train for the *Human-Cortex* dataset. Trials 8 and 9 might be outliers. **b** Filters of FLF models (Eq. (4)) fitted to data with and without suspected outliers. The latter remains mostly below the former for all t , which reduces the possibility of simulating unstable spike trains. **c** Diagnostic curves for models fitted before and after removing the suspected outliers: the model becomes stable after removal. Synthetic spike trains simulated from that more are indeed stable (not shown). (D,E,F) Same

analysis applied to spike trains generated from a two-rate *Izhikevich* model. **d** The dataset is composed of 16 spike trains with a high firing rate, and four with a low firing rate. **e** spike counts and deviations from the central spike train clearly identify two groups of spike trains. **f** Diagnostic curves of FLF models fitted to the full datasets (blue), and to the dataset after the four unusual spike trains are removed. The former diagnoses an unstable model, the latter a stable model. Spike trains simulated from the latter model are indeed stable (not shown)

time wrapped ST_2 , and the second penalizes the deviation of the time warping transformation from the identity function $\gamma(t) = t$. The central spike train \overline{ST} , is defined as

$$\overline{ST} = \arg \min_{C \in \mathcal{S}} \sum_{i=1}^n d(ST_i, C),$$

where \mathcal{S} is the set of all spike trains. We then compute each distance

$$d_i = d(\overline{ST}, ST_i), \quad i = 1, \dots, n$$

and use d_i to identify unusually discrepant trials.

The deviations d_i for the *Human-Cortex* spike trains are shown in Fig. 4a. Trials 8 and 9 have the largest values of d_i , and they also have large spike counts. After removing them, the fitted FLF model becomes stable, according to the diagnostic plot in Fig. 4c. Figure 4b

shows that the filter fitted after excluding the outliers lies mostly below the initial filter, which reduces the chance of simulation divergence. We note that if we remove only one of these trials the fitted model is again unstable. Furthermore, if we remove any other 2 trials the fitted model is unstable. Figure 4d, e and f shows that a similar analysis applied to data generated from *Izhikevich* models with two different firing rates – 16 spike trains have a large firing rate and four have a small firing rate – yields similar conclusions: that is, outlier trials can destabilize models, and careful data pre-processing to remove them might improve stability.

Different kinds of outliers may have to be treated differently. Outlier trials resulting from bad recordings should be removed. But absent such experimental difficulties it remains important to consider unusual features of the data, and to avoid models that fail to account for those features. In the synthetic two-rate *Izhikevich* dataset, for example, four




Fig. 5 Diagnostic curves of FNF_S models with $k = 2, 4, 5$ fitted to the *Human-Cortex* dataset. The dashed red lines are the models’ maximum firing rates. The largest model with $k = 5$ is unstable because

the diagnostic curve is above the first sequent after it last intersects it. The two other models are stable

trials are noticeably sparse, making a common rate model fit poorly. Methods based on models that allow for excess trial-to-trial variability are available (Ventura et al. 2005).

4 Stability of FNF models

To evaluate the performance of FNF models, we extend the method of Gerhard et al. (2017) to obtain a stability diagnostic, further allowing the baseline rate to be a time-varying function $\beta(t)$, as in Kass and Ventura (2001). If we approximate the firing rate before the last spike t_{1*} with the reciprocal of the mean ISI, $A_0 = 1/\tau$, and replace the ISIs by their expectation in (6), we obtain:

$$\log \lambda(t|H_t) \approx \beta(t) + \sum_{k=1}^k h_j(t - t_{1*} + (k - 1)\tau). \tag{9}$$

As in Section 2, we then use this approximation to derive the approximate PDF of the future ISI $t_* - t_{1*}$, and calculate the firing rate $\mathcal{L}_h(A_0)$ after t_{1*} as the reciprocal of the mean future ISI (see (6)). The diagnostic for a fitted model is again based on a plot of $\mathcal{L}_h(A_0)$ against A_0 , and its stability determined using the rules in the boxed text in Section 2. For example, Fig. 5 shows the diagnostics of three FNF_S models fitted to the *Human-Cortex* dataset described in Table 1, using the smooth basis in Pillow et al. (2008). The largest model (panel A) is unstable, in the sense that spike trains generated from that model could have unrealistically large number of spikes; the other two models are stable.

Just as in Gerhard et al. (2017), we can validate our FNF model stability diagnostic against spike train data.

For example, Fig. 6 shows the stability map for the FNF_S family of models with firing rate $\log \lambda(t|H_t) = \beta_0 + \sum_{j=1}^5 h(t - t_{j*})$, where $\beta_0 = -4$, $h(t) = \beta_1 B_1(t) + \beta_2 B_2(t)$, and $B_1(t) = e^{-t/0.02}$ and $B_2(t) = e^{-t/0.1}$ are the basis functions shown in the inset of Fig. 2a. For each value of (β_1, β_2) , we (i) simulated a 10 sec. long spike train from the model and deemed the model divergent if it generated over 900 spikes in the last second, (ii) produced the diagnostic curve and determined from it if the model was stable, fragile, or divergent, and (iii) plotted (β_1, β_2) against the




Fig. 6 Stability map for FNF_S models with firing rates $\log \lambda(t|H_t) = \beta_0 + \sum_{j=1}^5 h(t - t_{j*})$, where $\beta_0 = -4$, $h(t) = \beta_1 B_1(t) + \beta_2 B_2(t)$, $B_1(t) = e^{-t/0.02}$ and $B_2(t) = e^{-t/0.1}$. For each value of (β_1, β_2) , we (i) simulated a 10 sec. long spike train from the model and deemed the model unstable if it generated over 900 spikes in the last second, (ii) produced the diagnostic curve and determined from it if the model was stable, fragile, or divergent, and (iii) plotted (β_1, β_2) against the outcomes in (i), with unstable simulations indicated by black dots, and (ii), in colors. Our diagnostic is reliable because it matches the simulation well




Fig. 7 (a, b, c) AIC and (d, e, f) BIC values for several FLF, FNF_S, and FNF_M models fitted to three datasets. (FNF_S and FLF values are equal in panel F, and the latter mask the former.) Simulation unstable models and models that failed the original and/or the discrete KS test are

indicated by red squares and crosses. Many models are simulation stable; the FNF_M models fitted here are all simulation stable. Stable models that achieve a desirable criterion, e.g. low AIC, could be chosen

outcomes in (i) and (ii): the two match, which suggests that our diagnostic is reliable. The many FNF_M models we investigated also suggest that the diagnostic is reliable; we did not provide an example diagnostic map here because all these models were stable across the entire parameter space.

Figures 5 and 7c and f show that all FNF_S models with $k \leq 4$ and all FNF_M models fitted to the *Human-Cortex* dataset are stable. They also all pass the two KS tests so they are not obviously deficient. With many simulation stable models available, it may be desirable to choose one that also fits the data best according to some criterion. Figure 7c and f shows the Akaike Information Criterion (AIC) and Bayesian Information Criterion (BIC) for all these models. Small AIC and BIC values are desirable because AIC is an estimate of prediction risk, and BIC is inversely related to the posterior probability of fitting the correct model, in an asymptotic sense; BIC tends to prefer models with fewer parameters (Kass et al. 2014). Both criteria suggest that the FNF_S model with $k = 1$ fits best; it is also simulation stable. Figure 7 shows results from two additional examples. Among the stable models fitted to the bursty *Goldfish* dataset, the FNF_M

model with $k = 6$ filters fits best based on AIC, and FNF_S model with $k = 9$ fits best based on BIC. The synthetic *Izhikevich-burst* dataset is bursty as well; see Fig. 10a. Its best simulation stable models are FNF_M models with $k = 7$ and $k = 4$ according to AIC and BIC, respectively.

To summarize, our general strategy is to fit FNF models for several values of k and choose a model that is simulation stable and also fits the data well according to criteria such as the KS tests, and AIC or BIC. (Note that because AIC and BIC are obtained from a finite data sample, they have variability, so that similar values should be considered equal.) If no stable model can be found, a model that provides a good fit may be used after constraining its parameters to lie in the parameter subspace corresponding to stability, as Gerhard et al. (2017) suggest.

5 Comparison of FNF and FLF models

A key feature of FLF models is that they sum the effect of all spikes in the filter window of length T_h , which puts




Fig. 8 **a** *Goldfish* dataset spike trains and simulated spike trains from FLF, FNF_S ($k = 5$), and FNF_M ($k = 5$) models fitted to the dataset: despite modeling the effects of past spiking differently, both type of models can generate busts similar to those in the dataset. **b** Filters of the FNF_S models fitted to the *Goldfish* dataset with past number of spikes $k = 1, \dots, 9$. When $k \geq 5$, the filters are almost identical, suggesting that effects of spikes prior to 5 spikes back do not contribute much to the fits. The fitted FLF filter has length $T_h = 0.19$ sec., which

contains 4 past spikes on average; it overlaps with the FNF_S filters with $k \geq 5$, suggesting that these models are functionally similar (although FNF_S models are more likely to be stable). **c** Fitted filters of an FNF_M model with $k = 5$: the filters are substantially different, suggesting that burst behavior is captured by differentially weighing the contribution of previous spikes according to their timing and ordering. A likelihood ratio test comparing the FNF_S and FNF_M models with $k = 5$ strongly favors the latter ($p \ll 0.001$)

no limitation on the number of past spikes influencing the firing rate at t , even if T_h is short. Therefore, if a fitted intensity function has a rising trend, an increasing number of spikes could fall within the filter window, and this could increase the firing rate, eventually yielding unstable simulated spike trains. In contrast, FNF models (Eq. (3)) and also the extension to time-varying baseline rates) model history with a fixed number of spikes, k , and if the baseline rate $\beta(t)$ and all of the individual filters are bounded above, the firing rate will be bounded. Furthermore, by allowing multiple filters, FNF_M models can diminish the effects of multiple spikes that occur, somewhat infrequently, in close temporal proximity. Thus, in principle, FNF_M models tend to be stable, and we did not find any cases in which FNF_M models were unstable. See, for example, the results in Fig. 7. However, we have also seen that, in some cases, the fitted FNF_S firing rates can be large enough to become unstable (see Fig. 5a and panels c and f of Fig. 7), and for that reason we developed a stability diagnostic and a strategy to stabilize a divergent FNF model in Section 4. We could apply a similar strategy to FLF models, using several filter window lengths T_h in place of several values of k . Gerhard et al. (2017) fitted an FLF model with $T_h = 0.35$ sec to the *Human-Cortex* dataset, which was unstable. Figure 7c and f shows the stability status, AIC, and BIC values of fitted FLF models for several values of T_h . (FLN and FNF_S models have similar AIC and BIC values that are hard to distinguish from one another on the plots.) The FLF model with a very short filter length of $T_h = 0.177$ fits the data well (it passes both KS tests and has smallest AIC and BIC) and is stable. Thus, while FNF_M models seem to be inherently

less likely to be unstable, we can not make any universal comparative statement about stability, and, importantly, fitting with either type of model requires care. A remaining issue is whether there are interesting cases in which the additional flexibility of FNF_M models is useful. We now present a few additional comparative results.

Figure 7 provides a summary of fits for the *Human-Cortex* dataset. We see that FNF_S models have AIC and BIC values similar to, or smaller than FLF models. The FNF_M models have higher AIC, presumably because the additional flexibility of using several filters is not needed to fit the data well yet it increases complexity. On the other hand, the FNF models fitted to the *Izhikevich-burst* data set have smaller AIC and BIC values than the FLF models, and FNF_M models have smaller AIC and nearly all smaller BIC values than FNF_S models, presumably because the data are bursty and thus are not fitted adequately with simpler models. We also used a real data set, labeled *Goldfish*, which consists of recordings from retinal ganglion cells *in vitro* that exhibit bursting firing (Levine 1991; Tokdar et al. 2010); see Table 1 and Figure 8A. The AIC and BIC values are again smaller for most FNF models.

These comparisons are substantiated in Figs. 8 and 10. Figure 8a displays the *Goldfish* data spike trains together with simulated spike trains from a FLF model fitted to the data, having filter length $T_h = 0.19$ seconds containing five past spikes on average, as well as from fitted FNF_S and FNF_M models with $k = 5$: despite modeling the effects of past spiking differently, both type of models can generate busts similar to those observed in the data. Figure 8b displays the filters of FNF_S models fitted to the *Goldfish*

dataset with past number of spikes $k = 1$ to 9. When $k \geq 5$, the filters are almost identical, suggesting that effects of spikes prior to 5 spikes back do not contribute much to the fits. The overlaid fitted FLF filter with $T_h = 0.19$ sec. overlaps with the FNF_S filters with $k \geq 5$, suggesting that these models are functionally similar (although, based on our previous analysis, FNF_S models are more likely to be stable).

Models with a single filter, as in Fig. 8b, assume that the effect of any past spike t_{j^*} on the firing rate at time t depends only on the elapsed time $t - t_{j^*}$ without considering the number of spikes that may have occurred between t_{j^*} and t . For the *Goldfish* data, this is a questionable assumption: a likelihood ratio test (LRT) comparing FNF_S and FNF_M models with $k = 5$ strongly favors the latter ($p \ll 0.001$). Furthermore, the fitted filters of the FNF_M model, shown in Fig. 8c, are substantially different, suggesting that burst behavior is captured better by differentially weighing the contribution of previous spikes according to their timing and ordering. We may interpret these multiple distinct filters by observing several characteristics of the data (see Tokdar et al. 2010): the average burst length is roughly 25ms, a burst ISI is around 7ms, the median number of spikes in a burst is 4, and bursts occur, on average, roughly every 200 ms. With these in mind, the narrowness and height of the first filter suggests that the effect of the first spike back is strongly influenced by bursting, i.e., when a spike occurs less than 25 ms in the past it is likely that the cell is in a bursting state and the probability of spiking is increased; filters 2 to 4, corresponding to the 2nd to 4th spikes back, diminish the firing rate starting around 25 ms in the past, which presumably signals that when these multiple spikes back are spaced further than 25 ms in the past, the neuron has transitioned to a “down” state; the effect of the 5th spike back is to increase the firing rate after a longer duration, peaking around 200 ms in the past, reflecting an expectation that the neuron has already finished its pause after a burst and has now returned to the bursting state. Figure 10 in the appendix contains the corresponding plots for the synthetic *Izhikevich-inhomo* dataset, from which similar conclusions can be drawn.

In summary, FNF_M models do, sometimes, provide better fits than FLF or FNF_S models, but this is an empirical question that must be answered for each set of data separately. We should also note that models that incorporate hidden burst and non-burst states, as in Tokdar et al. (2010), may provide even better descriptions of bursting spike train data.

6 Discussion

We have attempted to provide a thorough analysis of the instability phenomenon identified by Gerhard et al.

(2017). We improved the diagnostic of Gerhard et al. (2017) and extended it to FNF models; we noted that time-varying baseline rates and excess trial-to-trial variability can cause instability of models that do not account for these effects; we introduced a method to detect outlier trials and illustrated its use; and we compared FNF with FLF models in several examples.

It is perhaps worth emphasizing that FNF_M models, with sufficiently large k , were always stable in the examples we investigated, regardless of whether there were stable FLF or FNF_S models. See, for example, Fig. 7. That figure, together with Figs. 8 and 10, also illustrate the way differing variations in spiking behavior may suggest different numbers of filters to use in an FNF model, according to standard model-fitting procedures.

Overall, we concluded that FNF_M models tend to avoid instability, and can provide helpful flexibility in some cases, but we cautioned that selection among the different FLF and FNF models must be done carefully based on the unique characteristics of particular data sets.

Our code is available on https://github.com/AlbertYuChen/Divergent_Spiketrain_public.git.

Acknowledgments Yu Chen and Robert E. Kass were supported by NIH grant OT2OD023859.

Robert E. Kass and Valérie Ventura were supported by NIH grant R01 MH064537.

Robert E. Kass was also supported, in part, by NSF grant IIS-1430208.

Compliance with Ethical Standards

Conflict of interest No potential conflict of interest was reported by the authors.

Appendix A: Datasets

Table 1 Details of the datasets used in this paper

Data	<i>Monkey</i>	<i>Human</i>	<i>Goldfish</i>
Feature	inhomogeneous	trial-to-trail variability	bursty
# Trials	10	10	1
Trial duration (sec)	1	10	30
Mean firing rate (Hz)	24.0	1.0	32.4
Source	Gerhard et al.	Gerhard et al.	Tokdar et al.

The *Monkey* and *Human* datasets (Gerhard et al. 2017) consist of single unit recordings from monkey cortex PMv and M1 areas, and from the neocortex of a person with a pharmacologically intractable focal epilepsy, respectively. The *Goldfish* dataset (Levine 1991; Tokdar et al. 2010) consists of recordings from retinal ganglion cells *in vitro* that exhibit bursting firing

Appendix B: Diagnostic Maps




Fig. 9 Stability maps for two FLF models (Eq. (4)) F_θ using the diagnostic of Gerhard et al. (2017) and our updated diagnostic. For each value of θ , we (i) simulated a 10 sec. long spike train from F_θ , and deemed the model unstable if it generated over 900 spikes in the last second, (ii) produced the diagnostic curve and determined from it if the model was stable/fragile/divergent, and (iii) plotted θ against the outcomes in (i) and (ii). **a** Reproduction of the stability map in Gerhard et al. (2017) Fig. 4, where F_θ is an FLF model with $\beta_0 = -5.3$ and $h(t) = \beta_1 \cdot B_1(t) + \beta_2 \cdot B_2(t) + \text{Dip}(t)$, where $B_1(t) = e^{-t/0.02}$,

$B_2(t) = e^{-t/0.1}$ and $\text{Dip}(t)$ is a negative window function modeling a 2 msec. refractory period, $\theta = (\beta_1, \beta_2)$, and filter length $T_h = 0.2$ sec. The maps suggest that the diagnostic is mostly reliable, except in small regions of the parameter spaces. **b** Our updated diagnostic for the same model matches the simulation better. **c** Stability map using the diagnostic of Gerhard et al. (2017) for F_θ an FLF model with $\beta_0 = -4$, $h(t) = \beta_1 \cdot B_1(t) + \beta_2 \cdot B_2(t)$. Basis $B_1(t)$ and $B_2(t)$ are the same as Fig. 2a. $\theta = (\beta_1, \beta_2)$, and filter length $T_h = 0.35$ sec. **d** Our updated diagnostic for the same model matches the simulation better

Appendix C: Simulation algorithms

Algorithms 1, 2, and 3 generate *Izhikevich-xx*, FLF, and FNF datasets, respectively.

Algorithm 1 Izhikevich simulation algorithm. The Izhikevich dynamical model can generate a rich family of biophysically realistic spike patterns (Izhikevich 2003, 2004), including time varying rate pike trains, tonic spikes, bursts, etc. A list of parameters to produce various effects is given in Weber and Pillow (2017).

```

1 Input: Parameters  $a, b, c, d$ . Time resolution  $\Delta$ . Time
   varying spiking intensity  $I(t)$ .
2 Initial:  $u(0) = 0, v(0) = 0, \mathbf{S} = \{0\}$ 
3 for  $t = 0$  to  $T$  do
4    $dv = 0.04v(t)^2 + 5v(t) + 140 - u(t) + I(t)$ 
5    $du = a(bv(t) - u(t))$ 
6    $v(t + 1) = v(t) + dv \cdot \Delta$ 
7    $u(t + 1) = u(t) + du \cdot \Delta$ 
8   if  $v(t + 1) > 30$  then
9      $v(t + 1) = c$ 
10     $u(t + 1) = u(t) + d$ 
11     $\mathbf{S} = \mathbf{S} \cup \{t + 1\}$ 
12  else
13    continue
14  end
15 end
16 Output:  $\mathbf{S}$ 

```

Algorithm 2 FLF model (Equation 2) simulation algorithm. This algorithm simulates ISIs from a unit rate exponential distribution and inverts them using the time rescaling theorem (Brown et al. 2002; Kass et al. 2014) to obtain the past spike times.

```

1 Input: time resolution  $\Delta$ , baseline  $\beta(t), t \in [0, T]$ , and
   post-spike filter  $h$  with length  $L$ ;
2 define  $f(s_1, s_2) := \sum_{t=s_1}^{s_2} \lambda(t|H_t)\Delta,$ 
    $0 \leq s_1 < s_2 \leq T$ , assume  $\lambda(t|H_t) \geq 0$ ;
3 Initial:  $\mathbf{S} = \emptyset$  be the set of spike time points;
4  $\lambda(t|H_t) = \beta(t)$ 
5  $t_{1*} = 0$ 
6 while TRUE do
7   draw one sample  $Z \sim \text{Exp}(1)$ ;
8   if  $f(t_{1*}, T) < Z$  then
9     return
10  else
11     $s = \arg \min_{\tau} \{f(t_{1*}, \tau) \geq Z\}$ 
12     $\mathbf{S} = \mathbf{S} \cup \{s\}$ 
13     $t_{1*} = s$ 
14    Update the firing rate function by adding the
      impact of the new spike to the future firing
      rate:  $\log \lambda(\tau + t|H_t) = \log \lambda(\tau + t|H_t) + h(\tau),$ 
      for all  $\tau \in [0, \min(L, T - t)]$ 
15  end
16 end
17 Output:  $\mathbf{S}, \lambda(t|H_t)$ 

```

Algorithm 3 FNF model (Equation 3) simulation algorithm.

```

1 Input: time resolution  $\Delta$ , baseline  $\beta(t)$ ,  $t \in [0, T]$ , and
   $k$  post-spike filter  $h_i$  with length  $L_i$ 
2 define  $f(s_1, s_2) := \sum_{t=s_1}^{s_2} \lambda(t|H_t)\Delta$ ,
   $0 \leq s_1 < s_2 \leq T$ ,  $\lambda(t|H_t) \geq 0$  is the total firing rate
3 Initial:  $\mathbf{S} = \emptyset$  be the set of spike time points
4  $\lambda(t|H_t) = \beta(t)$ 
5  $t_{1*}, t_{2*}, \dots, t_{k*} = 0$ 
6 while TRUE do
7   draw one sample  $Z \sim \text{Exp}(1)$ 
8   Update the firing rate function
    $\log \lambda(t|H_t) = \beta(t) + \sum_{i=1}^{\min(k, |\mathbf{S}|)} h_i(t - t_{i*})$ , if
    $t > L_i$ ,  $h_i(t) = 0$ .  $t_{i*}$  are the last  $i$ 'th spike.
9   if  $f(t_{1*}, T) < Z$  then
10    return
11  else
12     $s = \arg \min_{\tau} \{f(t_{1*}, \tau) \geq Z\}$ 
13     $\mathbf{S} = \mathbf{S} \cup \{s\}$ 
14     $t_{1*} = s, t_{2*} = t_{1*}, \dots, t_{k*} = t_{(k-1)*}$ 
15  end
16 end
17 Output:  $\mathbf{S}, \lambda(t|H_t)$ 

```

Appendix D: Misc. results

Derivation of Eq. (7)

$$\sum_{t_{j*} \in (t-T_h, t_{1*})} h(t - t_{j*}) \approx \mathbb{E}_N \left[\int_{t-T_h}^{t_{1*}} h(t - \tau) dN(\tau) \right] \tag{10}$$

$$= \mathbb{E}_{N_\Delta} \left[\mathbb{E}_{N|N_\Delta} \left[\int_{t-T_h}^{t_{1*}} h(t - \tau) dN(\tau) \mid N_\Delta \right] \right] \tag{11}$$

$$\stackrel{t-\tau=u}{=} \mathbb{E}_{N_\Delta} \left[\frac{N_\Delta}{t_{1*} - t + T_h} \int_{t-T_h}^{T_h} h(u) du \right] \tag{12}$$

$$= A_0 \int_{t-T_h}^{T_h} h(u) du \tag{13}$$

where $N_\Delta = N_{(t-T_h, t_{1*})}$ is the number of spikes in $(t - T_h, t_{1*})$, and A_0 is the mean firing rate in that time window. In Eq. (11), the inner expectation is taken over spike count conditioned on a fixed number of spikes in the interval $(t - T_h, t_{1*})$. If the filter $h(u)$ is estimated by $e^{h(u)} - 1$ in Gerhard et al. (2017), the error will be larger if $h(u)$ is not close to 0. Because the point process itself is unknown, the firing rate function is approximated under the assumption that it is a homogeneous Poisson process. For homogeneous Poisson process, if the number of events is fixed, they distribute evenly in the interval, which leads to Eq. (12).

The time rescaling theorem Let $Z_i = \int_{t_{i-1}}^{t_i} \lambda_0(t) dt$, where t_i are spike times, Z_i are time integral transformed intervals. Time rescaling theorem states that if $\lambda_0(t)$ is the firing rate




Fig. 10 **a** *Izhikevich-burst* synthetic dataset spike trains and simulated spike trains from FLF, FNF_S($k=4$), FNF_M($k=4$). Both type of models can generate bursts similar to those in the dataset. **b** Fitted filters of the FNF_S models with number of spikes $k = 1, \dots, 9$. When $k > 3$, the filters are very close to each other since further spikes will not make too much contribution to the future firing rate, thus will only affect the filter shape slightly. The fitted FLF filter overlaps with the FNF_S

filters with $k \geq 5$, suggesting that these models are functionally similar. **c** Fitted filters of an FNF_M model with $k = 4$: the filters are substantially different, which suggests that past spikes of different order have different effects on the firing rate. A likelihood ratio test comparing the FNF_S($k=5$) and FNF_M($k=5$) models favors the FNF_M model ($p \ll 0.001$)

of the true model, then Z_i are iid and $Z_i \sim \text{Exp}(1)$. The goodness-of-fit test checks how close the distribution of transformed intervals from estimated model is to the unit exponential distribution.

References

- Brown, E. N., Barbieri, R., Ventura, V., Kass, R. E., Frank, L. M. (2002). The time-rescaling theorem and its application to neural spike train data analysis. *Neural Computation*, *14*(2), 325–346.
- Chen, S., Shojaie, A., Shea-Brown, E., Witten, D. (2017). The multivariate Hawkes process in high dimensions: Beyond mutual excitation. arXiv:1707.04928.
- Eichler, M., Dahlhaus, R., Dueck, J. (2017). Graphical modeling for multivariate Hawkes processes with nonparametric link functions. *Journal of Time Series Analysis*, *38*(2), 225–242.
- Gerhard, F., Deger, M., Truccolo, W. (2017). On the stability and dynamics of stochastic spiking neuron models: Nonlinear Hawkes process and point process GLMs. *PLoS Computational Biology*, *13*(2), e1005390.
- Haslinger, R., Pipa, G., Brown, E. (2010). Discrete time rescaling theorem: determining goodness of fit for discrete time statistical models of neural spiking. *Neural Computation*, *22*(10), 2477–2506.
- Izhikevich, E. M. (2003). Simple model of spiking neurons. *IEEE Transactions on Neural Networks*, *14*(6), 1569–1572.
- Izhikevich, E. M. (2004). Which model to use for cortical spiking neurons? *IEEE Transactions on Neural Networks*, *15*(5), 1063–1070.
- Kass, R. E., & Ventura, V. (2001). A spike-train probability model. *Neural Computation*, *13*(8), 1713–1720.
- Kass, R.E., Eden, U.T., Brown, E.N. (2014). *Analysis of neural data* Vol. 491. New York: Springer.
- Levine, M. W. (1991). The distribution of the intervals between neural impulses in the maintained discharges of retinal ganglion cells. *Biological Cybernetics*, *65*(6), 459–467.
- Pillow, J. W., Shlens, J., Paninski, L., Sher, A., Litke, A. M., Chichilnisky, E., Simoncelli, E. P. (2008). Spatio-temporal correlations and visual signalling in a complete neuronal population. *Nature*, *454*(7207), 995–999.
- Tokdar, S., Xi, P., Kelly, R. C., Kass, R. E. (2010). Detection of bursts in extracellular spike trains using hidden semi-Markov point process models. *Journal of Computational Neuroscience*, *29*(1–2), 203–212.
- Ventura, V., Cai, C., Kass, R. E. (2005). Trial-to-trial variability and its effect on time-varying dependency between two neurons. *Journal of Neurophysiology*, *94*(4), 2928–2939.
- Weber, A.I., & Pillow, J.W. (2017). Capturing the dynamical repertoire of single neurons with generalized linear models. *Neural Computation*.
- Wu, W., & Srivastava, A. (2011). An information-geometric framework for statistical inferences in the neural spike train space. *Journal of Computational Neuroscience*, *31*(3), 725–748.